

PowerCube Assembled modules for MV primary switchgear

- 12-24 kV
- 630-4000 A
- 25-40 kA (3 s) - 50 kA (1 s)
- Modular structure
- Mechanical and electromechanical locks
- Metal shutters with fail safe device (optional)
- Apparatus racking-in/out with the door closed
- Earthing switch with or without making capacity

www.abb.com

